



Name WINDSOR ROAD UPGRADE

Client RTA of NSW



Project Description Daracon was engaged to construct 3.7km of 4 lane road, stormwater drainage, electrical services and public utilities such as power, telephone and water.

Site Location Vineyard

Value \$24.6 million

Duration Nov 04 – May 06

Referees Kevin Hays - 02 8814 2398

Key Personnel Project Manager – Garry Price
Supervisor - Rod Lang

- Significant Achievements**
- Detailed traffic switches were done often to provide for minimum impacts on 50,000+ ADT volume and maintaining safety of those working on site
 - 25,000m² of lean mix sub base 240mm thick was successfully hand placed by subcontractors De Martin Gasparini and achieved the tight time, cost and quality requirements of the specifications
 - Several heritage boundary stones circa 1825 were identified along the route, were protected then carefully relocated
 - Two large water mains (900mm and 500mm dia.) were re-laid across the site without incident or disruption

