



Name

MT THORLEY TAILINGS DAM

Client

Coal & Allied Mt Thorley Operations, Hunter Valley



Project Description

- Construct tailings dam at Mt Thorley mine
- Spread, trim and compact overburden delivered by mine during each night shift
- Raise dam wall in 1 metre lifts each day.

Site Location

Mt Thorley Coal Mine

Value

\$1 million

Duration

12 weeks

Referees

Phil Baker – 0428 659 003

Key Personnel

Project Manager – Gary Price
Supervisor – John Peterson

Significant Achievements

Safety was of paramount importance and Daracon implemented a comprehensive system that was accepted by CNA and other clients.

- The work involved the placement, trimming and compaction of over 1,000,000 cubic metres of overburden material
- Coordination between mine and Daracon personnel was imperative to the smooth flow of the work
- Up to 30,000 cu m of overburden was delivered during each night shift by mine personnel, which was spread and finished in 900mm layers by Daracon

Extent of Involvement & Role of Proponent (S)

Daracon was the principle contractor on this project. Landpac Technologies Pty Ltd was the only subcontractor utilized for the hire of an Impact Roller.

DARACON

Group



Shaping the Future

PROJECT PROFILE

